BILL #26-193 2026 Inflow and Infiltration Reduction Project



Project Location:

- South, Middle and North Lake Park
- Muth Rd., Fairlawn Ave., and Taylor Rd.
- Oakwood Dr. and Maple St.
- Arlington Ave. and Millsboro Rd.

Project Summary:

- Construction Estimate: $1,000,000
- Funding Sources:
  - OPWC $500,000
  - Sewer Fund $500,000
- Construction: Nov 2026 – Aug 2027

Project Description:

This project will use a trenchless technology known as “Cured-In-Place-Pipe Lining” to line 16,300 feet of pipe ranging from 8” to 21” in diameter. A new pipe is formed within the existing pipe using a resin liner. The pipe is steam cured and formed to the existing pipe, providing a “new” pipe with a design life of at least 50 years.



BEFORE



AFTER